

Contents

Part I Project Implementation Background

1	Locational Features of Dalian Lake	3
1.1	Geographical Location	3
1.2	Natural Conditions	4
1.3	Social Economic Conditions	8
	Bibliography	12
2	Regional Evolution of Dalian Lake.....	13
2.1	Regional Wetland Type.....	13
2.2	Regional Wetland Biology.....	15
2.2.1	Plankton.....	15
2.2.2	Aquatic Vascular Bundle Plants	17
2.2.3	Zoobenthos.....	18
2.2.4	Fishes.....	19
2.2.5	Birds	19
2.2.6	Animals	19
2.2.7	Endangered Rare Species.....	19
2.2.8	Invasive Species	20
2.3	Regional Wetland Evolution.....	20
2.3.1	Kinds of Phytoplankton and Evolution of Dominant Species	21
2.3.2	Kinds and Quantity Evolution of Zooplankton.....	21
2.3.3	Type, Quantity and Distribution Evolution of Aquatic Vascular Bundle Plants	21
2.3.4	Type, Quantity Distribution and Evolution of Benthic Organism	24
2.3.5	Composition, Distribution Characteristics and Aquatic Product Types of Fishes in Dianshan Lake.....	25
	Bibliography	26

3	Characteristics of Hydrologic Environment	27
3.1	Hydrologic Characteristics.....	27
3.2	Physical and Chemical Characteristics of Water Environment.....	29
3.3	Biological Characteristics of Water Environment.....	32
3.3.1	Density of Phytoplankton.....	32
3.3.2	Chlorophyll <i>a</i> Content of Phytoplankton in Dalian Lake.....	34
3.3.3	Density of Zooplankton.....	34
3.3.4	Density of Zoobenthos and Biomass in Dalian Lake.....	35
4	Analysis on Pollution Source	37
4.1	Internal Source Pollution.....	38
4.2	Non-point Source Pollution.....	40
4.2.1	Farm Chemical Fertilizer Pollution.....	40
4.2.2	Animal Husbandry Pollution.....	40
4.2.3	Fishery Breeding Pollution.....	41
4.3	Point Source Pollution.....	41
4.3.1	Pollution by Rural Life.....	41
4.3.2	Pollution by Industries.....	41
	Bibliography.....	42

Part II Project Planning, Design and Construction

5	Wetland Restoration Strategy	45
5.1	Evaluation on Status of Dalian Lake Wetland.....	45
5.1.1	Analysis on Ecological Functions of Dalian Lake Wetland.....	45
5.1.2	Integrated Evaluation on Status Quo of Dalian Lake Wetland.....	48
5.2	Wetland Restoration Thinking.....	50
5.2.1	Effect After Dalian Lake Wetland Is Rehabilitated.....	50
5.2.2	Restoration Strategy of Dalian Lake Wetland.....	51
5.2.3	Management Measures of Wetland.....	53
5.3	Philosophy and Principle for Planning and Designing on Wetland Restoration Project.....	54
5.3.1	Design Philosophy of Wetland Restoration.....	54
5.3.2	Design Principle of Wetland Restoration.....	55
5.4	Overall Planning for Wetland Restoration Project.....	56
5.4.1	Project and Its Significance.....	56
5.4.2	Project Planning Objective and Overall Thinking.....	57
5.4.3	Planning Content and Scale of Project.....	57
5.4.4	Anticipated Effect of Project.....	58
	Bibliography.....	61

6	Wetland Restoration Project Layout and Subarea Design.....	63
6.1	General Engineering Layout	63
6.1.1	Wetland Restoration and Reconstruction Area (Subarea A).....	63
6.1.2	Forest Wetland Cultivation Area (Subarea B)	64
6.1.3	Shoal Wetland Restoration and Biodiversity Conservation Area (Subarea C).....	65
6.2	Engineering Subarea Design	65
6.2.1	Design of Wetland Restoration and Reconstruction Area	65
6.2.2	Design of Forest Wetland Cultivation Area.....	72
6.2.3	Design of Shoal Wetland Restoration and Diversity Conservation Area	74
6.3	Water Conservation and Earthwork Design of the Project.....	76
6.3.1	The Work Conservation Design of the Project.....	76
6.3.2	Earthwork Project.....	82
7	Other Designs for Wetland Restoration Project.....	83
7.1	Construction Organization Design.....	83
7.1.1	Engineering Conditions.....	83
7.1.2	Drained Waters in Construction Period.....	85
7.1.3	Construction Methods	85
7.1.4	Construction Layout.....	86
7.1.5	Soil Balance	87
7.1.6	Construction Area.....	87
7.1.7	Construction Progress	87
7.1.8	The Main Machinery Equipment for the Construction ...	88
7.1.9	The Main Technical and Economic Indexes for the Construction.....	88
7.2	Environment Protection Design	88
7.2.1	Environment Protection Goals	89
7.2.2	Environment Protection Standard	90
7.2.3	Analysis and Appraisal for the Affection of Project Construction on Environment.....	90
7.2.4	Environment Protection Design	93
7.2.5	Environmental Management and Monitoring Plan	95
7.3	Water and Soil Conservation Design.....	96
7.3.1	Design Basis.....	96
7.3.2	Fundamental Principle	97
7.3.3	The Status Quo of Water and Soil Loss	97
7.3.4	Earthwork Balance	98
7.3.5	The Responsibility Scope and Subarea of Water and Soil Loss Prevention and Control	98
7.3.6	The Analysis of the Affection of Development and Construction Activities on Water and Soil Loss	99
7.3.7	The Goal of Water and Soil Loss Prevention and Control.....	99

	7.3.8	Measures of Water and Soil Loss Prevention and Control.....	100
	7.3.9	Water and Soil Loss Monitoring	102
7.4	Project	Management and Maintenance	102
	7.4.1	Management Institution and Personnel Composition	102
	7.4.2	Management Scope and Contents	103
	7.4.3	Water Quality Monitoring and Biological Investigation	104
	7.4.4	Annual Operation and Management Cost	104
	7.4.5	Project Operation and Management.....	105
	7.4.6	Planting and Management Methods of Wetland Plants.....	106
	7.4.7	Management Laws and Regulations	108
8		Construction and Management of the Project	109
	8.1	Construction Overview of the Project	109
	8.1.1	Basic State of the Project	109
	8.1.2	Construction Characteristics of the Project.....	109
	8.1.3	Overall Construction Layout.....	110
	8.2	Construction Organization and On-site Management.....	110
	8.2.1	Construction Organization Structure.....	110
	8.2.2	Construction On-site Management	112
	8.3	Construction Solution of the Project	112
	8.3.1	Main Construction Procedure	112
	8.3.2	Construction Preparation and Temporary Facilities.....	113
	8.3.3	On-site Clean Up.....	114
	8.3.4	Earthwork Digging and Refilling	114
	8.3.5	Quick Percolation System Filling	115
	8.3.6	Plant Planting	116
	8.4	Construction Progress and Guarantee System of the Project.....	116
	8.4.1	Construction Progress and the Goals of Construction Period	116
	8.4.2	Quality Guarantee System and Guarantee Measures of the Project	116
	8.4.3	Safety Guarantee System and Safety Guarantee Measures.....	118
	8.4.4	Technical Measures of the Construction in Winter and Monsoon	119
	8.4.5	On-site Civilized Construction Measures	120
	8.4.6	Construction Management and Others.....	120
	8.5	Supervision of the Project	120
	8.5.1	Supervision Goals and Guidance	120
	8.5.2	Supervision Institution	122
	8.5.3	Task and Method of Investment Control	123

8.5.4	Tasks and Methods of Progress Control	124
8.5.5	The Tasks and Methods of Quality Control.....	125
8.5.6	The Supervision Method of Defect Responsibility Period.....	126

Part III Effect Monitoring and Appraisal

9	Wetland Water Quality Monitor and Appraisal.....	129
9.1	The Water Quality Monitoring Layout and Appraisal Methods of the Project	129
9.1.1	Monitoring Layout and Time	129
9.1.2	Water Quality Monitoring and Appraisal Methods	129
9.2	The Monitoring Results of the Water Quality of the Project.....	131
9.2.1	The Physical Property of the Water.....	131
9.2.2	The Chemical Property of Water.....	133
9.2.3	The Biological Nature of Water	139
9.3	Other Monitoring Results of Wetland	142
9.3.1	Monitoring Results from Commissioned Unit.....	142
9.3.2	Monitoring Results from Other Units	142
	Bibliography	147
10	Benefit Appraisal of the Wetland	149
10.1	The Ecological and Environmental Benefit of the Project.....	149
10.1.1	Ecological Benefit.....	149
10.1.2	Environmental Benefit	150
10.2	Social and Economic Benefit of the Project	151
	Bibliography	153
	Appendices.....	155
	Appendix 1.....	155
	Appendix 2.....	159
	Attachment 2.1. Environment Quality Standard for Surface Water of the People's Republic of China	159
	Attachment 2.2. The Implementation Guidelines of the Protective Regulations of the Water Source of the Upper Reaches of Huangpu River in Shanghai.....	174
	Appendix 3.....	183
	Attached Figures 1. Overall Plan Maps of Shanghai Dalian Lake Wetland Restoration Project (2,000 mu)	183
	Attached Figures 2. Design Drawings of First-Stage Wetland Restoration Project (625 mu).....	195
	Attached Figures 3. Effect Figures of Wetland Restoration Project (150 mu).....	212
	Postscript & Testimonials.....	215